



Republic of the Philippines  
**ROMBLON STATE UNIVERSITY**  
 Odiongan, Romblon  
 Tel No. (042) 567-5273  
 Email: [romblonstateu@gmail.com](mailto:romblonstateu@gmail.com)  
 URL: [rsu.edu.ph](http://rsu.edu.ph)

**BIDS AND AWARDS COMMITTEE**

**ABSTRACT OF QUOTATION**  
**Solicitation No. RSU-2022-02-015**  
**ABC: PhP9,737,429.55**  
**QTY: 293**


**Upgrade of RSU Main and Satellite Campus CAN**

UNIT	ITEM DESCRIPTION	QTY	ESTIMATED UNIT COST	ESTIMATED COST
pcs	SFP module 1.25 Gbps	20		
pcs	SFP Module 10Gbase Transceiver	6		
pcs	Access controller for Access point	10		
pcs	Gigabit router dual core (5-port Gigabit Ethernet, Dual Core 880MHz CPU, 256MB RAM, USB, Bandwidth Management Router)	23		
pcs	Wireless AP for In-door (Dual Band Ceiling Mount Access Point, Qualcomm, 1300Mbps at 5GHz + 450Mbps at 2.4GHz, 1 Gigabit LAN, 802.3at PoE, 6 Internal Antennas, Band Steering, Centralized Management, Captive Portal, Load Balance, Rate Limit, VLAN)	26		
pcs	Wireless AP for out-door (Dual Band, 120 Deg Directional, 1300Mbps at 5GHz + 450Mbps at 2.4GHz, 1 Gigabit LAN, 802.3at PoE, Band Steering, Centralized Management, Captive Portal, Load Balance, Rate Limit)	16		
pcs	42U Data storage Cabinet including ventilation fan. Material: SPCC cold rolled sheet, thickness mounting profile 2.0mm, others 1.2mm, floor standing cabinet, 1 pc double open door with handle lock, 1 pc single open vented rear door with small round lock, 2 pcs removable side panel, 4 pcs mounting profile, 4 pcs mounting angle, fans with plugs, disassembled packing	2		
pcs	Main Router. 1U rackmount, 8x Gigabit Ethernet, 2xSFP+ cages, LCD, 36 cores x 1.2GHz CPU, 8GB RAM, Dual PSU	1		
pcs	Layer 3 Manage switch. 28-Port Gigabit L3 Managed Switch, 24 Gigabit RJ45 Ports, 4 Combo Gigabit SFP Slots, 2 Integrated 10G SFP+ Slots, 2 Optional 10G SFP+ Slots, RJ45	3		
pcs	Rock Mounter Server with Intel xeon processor 6C/6T, 16gb ddr4 x 4, 2Tb x 2hdd 7200rpm raid configuration, windows server 2019 essentials, dual Lan slot for teaming, single cable power supply 350w, including logistics and installation, 2 years vendor support, 2 years warranty, keyboard, mouse	2		
pcs	15U Data cabinet	16		




**BIDS AND AWARDS COMMITTEE**

pcs	Smart switch. 24-Port Gigabit Smart Switch, 24 Gigabit RJ45 Ports, 4 SFP Slots, 1U 19-inch Rack-mountable Steel Case, Static Routing, 802.1Q VLAN, STP/RSTP/MSTP, IGMP Snooping, 802.1p/DSCP QoS, ACL, 802.1x, Radius/Tacacs+ Authentication, LACP, CLI, SNMP, Dual Image, IPv6	16		
lot	b. Installation and Cabling Works with complete hardwares and accessories, quantities as per needed	1		
	Including:			
	1/2" Ø Flexible hose & Plastic Moulding			
	I/O port cat6			
	Utility box			
	RJ45 cable for CAT6			
	Network Cable Tray			
	Fiber toolkit with hard case			
	Fiber media converter			
	Ramp Cable protection 1M			
	Fiber optic single core mode,			
	CAT6 UPT cable Pure copper			
	CAT6 UTP Outdoor cable Pure Copper			
	8 gang power distribution unit			
	Cable management Guide			
	1U Cable management guide for switches			
	1U Patch Panel 24 port cat6			
	SC port			
	Rubber boots for CAT6			
	Outdoor Data Cabinet (can hold UPS & other network Equipment)			
	1" Ø Conduits PVC pipe for fiber optic protection,			
	Media converter chassis. housing for fiber media converter			
	Fiber optic 2 core. Single mode,			
<b>II. Campus Area Network and Backup NOC Equipment's with Installation and Cabling works (Romblon Campus)</b>				
pcs	Gigabit router dual core (5-port Gigabit Ethernet, Dual Core 880MHz CPU, 256MB RAM, USB, Bandwidth Management Router)	1		
pcs	Wireless AP for In-door (Dual Band Ceiling Mount Access Point, Qualcomm, 1300Mbps at 5GHz + 450Mbps at 2.4GHz, 1 Gigabit LAN, 802.3at PoE, 6 Internal Antennas, Band Steering, Centralized Management, Captive Portal, Load Balance, Rate Limit, VLAN )	3		
pcs	Wireless AP for out-door (Dual Band, 120 Deg Directional, 1300Mbps at 5GHz + 450Mbps at 2.4GHz, 1 Gigabit LAN, 802.3at PoE, Band Steering, Centralized Management, Captive Portal, Load Balance, Rate Limit)	3		
set	42U Data storage Cabinet including ventilation fan. Material: SPCC cold rolled	1		



**BIDS AND AWARDS COMMITTEE**

	sheet, thickness mounting profile 2.0mm, others 1.2mm, floor standing cabinet, 1 pc double open door with handle lock, 1 pc single open vented rear door with small round lock, 2 pcs removable side panel, 4 pcs mounting profile, 4 pcs mounting angle, fans with plugs, disassembled packing			
set	Main Router. 1U rackmount, 8x Gigabit Ethernet, 2xSFP+ cages, LCD, 36 cores x 1.2GHz CPU, 8GB RAM, Dual PSU	1		
set	Layer 3 Manage switch. 28-Port Gigabit L3 Managed Switch, 24 Gigabit RJ45 Ports, 4 Combo Gigabit SFP Slots, 2 Integrated 10G SFP+ Slots, 2 Optional 10G SFP+ Slots, RJ45	1		
set	Rock Mounter Server with Intel Xeon processor 6C/6T, 16gb ddr4 x 4, 2Tb x 2hdd 7200rpm raid configuration, windows server 2019 essentials, dual Lan slot for teaming, single cable power supply 350w, including logistics and installation, 2 years vendor support, 2 years warranty, keyboard, mouse	1		
set	15U Data cabinet	1		
lot	b. Installation and Cabling Works with complete hardware's and accessories, quantities as per needed	1		
	Including:			
	1/2" Ø Flexible hose & Plastic Moulding			
	I/O port cat6			
	Utility box			
	RJ45 cable for CAT6			
	Network Cable Tray			
	Ramp Cable protection 1M			
	Access controller for AP			
	CAT6 UPT cable Pure copper			
	8 gang power distribution unit			
	Cable management			
	1U Cable management guide for switches			
	1U Patch Panel 24 port cat6			
	Rubber boots for CAT6			
<b>III. Campus Area Network Equipment's with Installation and Cabling works (7 Satellite Campuses)</b>				
pcs	Gigabit router dual core (5-port Gigabit Ethernet, Dual Core 880MHz CPU, 256MB RAM, USB, Bandwidth Management Router)	7		
pcs	Wireless AP for In-door (Dual Band Ceiling Mount Access Point, Qualcomm, 1300Mbps at 5GHz + 450Mbps at 2.4GHz, 1 Gigabit LAN, 802.3at PoE, 6 Internal Antennas, Band Steering, Centralized Management, Captive Portal, Load Balance, Rate Limit, VLAN )	21		
pcs	Wireless AP for out-door (Dual Band, 120 Deg Directional, 1300Mbps at 5GHz + 450Mbps at 2.4GHz, 1 Gigabit LAN,	21		



**BIDS AND AWARDS COMMITTEE**

	802.3at PoE, Band Steering, Centralized Management, Captive Portal, Load Balance, Rate Limit)			
sets	Smart Switch. 24-Port Gigabit Smart Switch, 24 Gigabit RJ45 Ports, 4 SFP Slots, 1U 19-inch Rack-mountable Steel Case, Static Routing, 802.1Q VLAN, STP/RSTP/MSTP, IGMP Snooping, 802.1p/DSCP QoS, ACL, 802.1x, Radius/Tacacs+ Authentication, LACP, CLI, SNMP, Dual Image, IPv6	7		
sets	15U Data cabinet	7		
lot	b. Installation and Cabling Works with complete hardwares and accessories, quantities as per needed	1		
	Including:			
	1/2" Ø Flexible hose & Plastic Moulding			
	Utility box			
	RJ45 cable for CAT6			
	Network Cable Tray			
	Ramp Cable protection 1M			
	Access controller for AP			
	CAT6 UPT cable Pure copper			
	Rubber boots for CAT6			
<b>IV. 15KW Solar Power Generator for RSU Main CAN and NOC with complete Accessories with Installation</b>				
Equipment List				
pcs	500W Solar Panel	30		
set	Solar charge controller for 15KW Solar Power Generator system	2		
set	15KW Solar inverter	1		
pcs	100AH Lifepo4 battery	16		
lot	AC and DC Connecting kit, railings, duct, etc	1		
lot	Design, Installation, Testing and Commission of DC and AC line protection/ distribution box, wire duct and solar cable	1		
<b>V. 3KW Solar Power Generator for RSU Romblon CAN and NOC with complete Accessories with installation</b>				
pcs	300W Solar Panel	10		
pcs	3Kw Solar inverter	1		
pcs	60-amp Solar charge controller	2		
pcs	100AH Lifepo4 battery	8		
lot	AC and DC Connecting kit, railings, duct, etc	1		
lot	Design, Installation, Testing and Commission of DC and AC line protection/ distribution box, wire duct and solar cable	1		
<b>TOTAL</b>		<b>293</b>		



Republic of the Philippines  
**ROMBLON STATE UNIVERSITY**  
Odiongan, Romblon  
Tel No. (042) 567-5273  
Email: [romblonstateu@gmail.com](mailto:romblonstateu@gmail.com)  
URL: [rsu.edu.ph](http://rsu.edu.ph)

---

---

**BIDS AND AWARDS COMMITTEE**

---

---

---

Name and Signature of the Bidder/Authorized Representative

---

Name of the Company