



SPECIFICATIONS Solicitation No. RSU-2024-11-099 ABC: PhP16,961,600.00

REFURBISHMENT OF RSU GYMNASIUM AT THE MAIN CAMPUS

Location: Romblon State University, Main CampusDuration: 120 Calendar Days

The project will be located at Romblon State University- Main Campus. The Description of work to be done are the following:

| Item No: | Description | Qty. | Unit | Statement of Compliance |
|-------------|---|------|------|----------------------------|
| 1 | Refurbishment of University Quadrangle | | | |
| | Scope of Work: | | | |
| | I. Airconditioning Units Works (5 units) | | | |
| | Split Type AC Floor Mounted Units (20.0 TR) (5 units) Cooling capacity: 250 kcal/m^2 x 1,750 m^2 = 437,500 kcal/h (144.7 TR) Unit selection: FTXS-M Series (20.0 TR) Indoor Unit: FTXS35-40KVJU (12-15 HP) Outdoor Unit: RXSQ35-40PVJU (12-15 HP) Airflow: 30,000-40,000 CMH Power supply: 3-phase, 380-415V, 50Hz Dimensions: Indoor: 1,300 x 400 x 300 mm Outdoor: 1,800 x 900 x 750 mm Weight: 350 kg (indoor), 450 kg (outdoor) Piping and insulation (5 units) Controls and accessories (5 units) | 1 | ls | |
| TOTAL | | 1 | LS | |

Name and Signature of the Bidder/Authorized Representative

Name of the Company